YOUR ONESURVEY HOME REPORT



Bonnie View Craig, Plockton IV52 8UB

PREPARED FOR

Craig Grant

INSPECTION CARRIED OUT BY:

SELLING AGENT:





HOME REPORT GENERATED BY:



Document Index

Document	Status	Prepared By	Prepared On
Index of Documents			
Single Survey	Final	Graham & Sibbald LLP - Inverness	08/06/2023
Mortgage Certificate	Final	Graham & Sibbald LLP - Inverness	08/06/2023
Property Questionnaire	Final	Mr. Craig Grant	05/06/2023
EPC	File Uploaded	Graham & Sibbald LLP - Inverness	07/06/2023

Important Notice:

This report has been prepared for the purposes and use of the person named on the report. In order to ensure that you have sight of a current and up to date copy of the Home Report it is **essential** that you visit www.onesurvey.org (free of charge) to download a copy personalised in your own name. This enables both Onesurvey and the Surveyor to verify that you have indeed had sight of the appropriate copy of the Home Report prior to your purchasing decision. This personalised report can then be presented to your legal and financial advisers to aid in the completion of your transaction. Failure to obtain a personalised copy may prevent the surveyor having any legal liability to you as they will be unable to determine that you have relied on this report prior to making an offer to purchase.

Neither the whole, nor any part of this report may be included in any published document, circular or statement, nor published in any way without the consent of Onesurvey Ltd. Only the appointed Chartered Surveyor can utilise the information contained herein for the purposes of providing a transcription report for mortgage/loan purposes.



SINGLE Survey

A report on the condition of the property, with categories being rated from 1 to 3.



Single Survey

Survey report on:

Surveyor Reference KD2023	3060015
---------------------------	---------

Customer	Mr. Craig Grant
----------	-----------------

Selling address	Bonnie View Craig, Plockton IV52 8UB
-----------------	--

Date of Inspection	06/06/2023
--------------------	------------

Prepared by

PART 1 - GENERAL

1.1 THE SURVEYORS

The Seller has engaged the Surveyors to provide the Single Survey Report and a generic Mortgage Valuation Report for Lending Purposes. The Seller has also engaged the Surveyors to provide an Energy Report in the format prescribed by the accredited Energy Company.

The Surveyors are authorised to provide a transcript or retype of the generic Mortgage Valuation Report on to Lender specific pro-forma. Transcript reports are commonly requested by Brokers and Lenders. The transcript report will be in the format required by the Lender but will contain the same information, inspection date and valuation figure as the generic Mortgage Valuation Report and the Single Survey. The Surveyors will decline any transcript request which requires the provision of information additional to the information in the Report and the generic Mortgage Valuation Report until the Seller has conditionally accepted an offer to purchase made in writing.

Once the Seller has conditionally accepted an offer to purchase made in writing, the Purchaser's lender or conveyancer may request that the Surveyors provide general comment on standard appropriate supplementary documentation. In the event of a significant amount of documentation being provided to the Surveyors, an additional fee may be incurred by the Purchaser. Any additional fee will be agreed in writing.

If information is provided to the Surveyors during the conveyancing process which materially affects the valuation stated in the Report and generic Mortgage Valuation Report, the Surveyors reserve the right to reconsider the valuation. Where the Surveyors require to amend the valuation in consequence of such information, they will issue an amended Report and generic Mortgage Valuation Report to the Seller. It is the responsibility of the Seller to ensure that the amended Report and generic Mortgage Valuation Report are transmitted to every prospective Purchaser.

The individual Surveyor will be a member of the Royal Institution of Chartered Surveyors who is competent to survey, value and report upon Residential Property. ¹

If the Surveyors have had a previous business relationship within the past two years with the Seller or Sellers Agent or relative to the property, they will be obliged to indicate this by ticking the adjacent box.

 $\overline{\mathcal{M}}$

The Surveyors have a written complaints handling procedure. This is available from the offices of the Surveyors at the address stated.

1.2 THE REPORT

The Surveyors will not provide an amended Report on the Property, except to correct factual inaccuracies.

¹ Which shall be in accordance with the current RICS Valuation Standards (the Red Book) and RICS Codes of Conduct

The Report will identify the nature and source of information relied upon in its preparation.

The Surveyor shall provide a Market Value of the Property, unless the condition of the Property is such that it would be inappropriate to do so. A final decision on whether a loan will be granted rests with the Lender who may impose retentions in line with their lending criteria. The date of condition and value of the property will be the date of inspection.

To date, Purchasers have normally obtained their own report from their chosen Surveyor. By contrast, a Single Survey is instructed by the Seller and made available to all potential Purchasers in expectation that the successful Purchaser will have relied upon it. The Royal Institution of Chartered Surveyors rules require disclosure of any potential conflict of interest when acting for the Seller and the Purchaser in the same transaction. The Single Survey may give rise to a conflict of interest and if this is of concern to any party they are advised to seek their own independent advice.

The Report and any expressions or assessments in it are not intended as advice to the Seller or Purchaser or any other person in relation to an asking price or any other sales or marketing decisions.

The Report is based solely on the Property and is not to be relied upon in any manner whatsoever when considering the valuation or condition of any other property.

If certain minor matters are mentioned in the Report it should not be assumed that the Property is free of other minor defects.

Neither the whole nor any part of the Report may be published in any way, reproduced or distributed by any party other than the Seller, prospective purchasers and the Purchaser and their respective professional advisers without the prior written consent of the Surveyors.

1.3 LIABILITY

The Report is prepared with the skill and care reasonably to be expected of a competent residential surveyor who is a member of the Royal Institution of Chartered Surveyors.

The Report is addressed to the Seller and was prepared in the expectation that it (or a complete copy) along with these Terms and Conditions (or a complete copy) would (or, as the case might be, would have been) be disclosed and delivered to

- the Seller;
- any person(s) noting an interest in purchasing the Property from the Seller;
- any person(s) who make(s) (or on whose behalf is made) an offer to purchase the Property, whether or not that offer is accepted by the Seller;
- the Purchaser; and
- the professional advisers of any of these.

The Surveyors acknowledge that their duty of skill and care in relation to the Report is owed to the Seller and to the Purchaser. The Surveyors accept no responsibility or liability whatsoever in relation to the Report to persons other than the Seller and the Purchaser. The Seller and Purchaser should be aware that if a Lender seeks to rely on this Report they do so at their own risk. In particular, the Surveyors accept no responsibility or liability whatsoever to any Lender in relation to the Report. Any such Lender relies upon the Report entirely at their own risk.

1.4 GENERIC MORTGAGE VALUATION REPORT

The Surveyors undertake to the Seller that they will prepare a generic Mortgage Valuation Report, which will be issued along with the Single Survey. It is the responsibility of the Seller to ensure that the generic Mortgage Valuation Report is provided to every potential Purchaser.

1.5 TRANSCRIPT MORTGAGE VALUATION FOR LENDING PURPOSES

The Surveyors undertake that on being asked to do so by a prospective purchaser, or his/her professional advisor or Lender, they will prepare a Transcript Mortgage Valuation Report for Lending Purposes on terms and conditions to be agreed between the Surveyors and Lender and solely for the use of the Lender and upon which the Lender may rely. The decision as to whether finance will be provided is entirely a matter for the Lender. The Transcript Mortgage Valuation Report will be prepared from information contained in the Report and the generic Mortgage Valuation Report. 2

1.6 INTELLECTUAL PROPERTY

All intellectual property rights whatsoever (including copyright) in and to the Report, excluding the headings and rubrics, are the exclusive property of the Surveyors and shall remain their exclusive property unless they assign the same to any other party in writing.

1.7 PAYMENT

The Surveyors are entitled to refrain from delivering the Report to anyone until the fee and other charges for it notified to the Seller have been paid. Additional fees will be charged for subsequent inspections and Reports.

1.8 CANCELLATION

The Seller will be entitled to cancel the inspection by notifying the Surveyor's office at any time before the day of the inspection.

The Surveyor will be entitled not to proceed with the inspection (and will so report promptly to the Seller) if after arriving at the property, the Surveyor concludes that it is of a type of construction of which the surveyor has insufficient specialist knowledge to be able to provide the inspection satisfactorily. The Surveyor will also be entitled not to proceed if after arriving at the property, the surveyor concludes that the property is exempt under Part 3 of The Housing (Scotland) Act 2006 as detailed in the (Prescribed Documents) Regulations 2008. If there is a potential threat to their health or personal safety, the inspection may be postponed or cancelled, at the Surveyor's discretion.

In the case of cancellation or the inspection not proceeding, the Surveyor will refund any fees paid by the Seller for the inspection and Report, except for

expenses reasonably incurred and any fee due in light of the final paragraph of this section.

In the case of cancellation by the Seller, for whatever reason, after the inspection has taken place but before a written report is issued, the Surveyor will be entitled to raise an Invoice equivalent to 80% of the agreed fee.

1.9 PRECEDENCE

If there is any incompatibility between these Terms and Conditions and the Report, these Terms and Conditions take precedence.

1.10 **DEFINITIONS**

- the "Lender" is the party who has provided or intends or proposes to provide financial assistance to the Purchaser towards the purchase of the Property and in whose favour a standard security will be granted over the Property;
- the "Transcript Mortgage Valuation Report for Lending Purposes" means a separate report, prepared by the Surveyor, prepared from information in the Report and the generic Mortgage Valuation Report, but in a style and format required by the Lender. The Transcript Mortgage Valuation Report for Lending Purposes will be prepared with the skill and care reasonably to be expected from a surveyor who is a member of the Royal Institution of Chartered Surveyors and who is competent to survey, value and report on the Property;
- the "Generic Mortgage Valuation Report" means a separate report, prepared by the Surveyor from information in the Report but in the Surveyor's own format.
- the "Market Value" is The estimated amount for which a property should exchange on the date of valuation between a willing buyer and a willing seller in an arm's-length transaction after proper marketing wherein the parties had each acted knowledgeably, prudently and without compulsion
- the "Property" is the property which forms the subject of the Report;
- the "Purchaser" is the person (or persons) who enters into a contract to buy the Property from the Seller;
- a "prospective Purchaser" is anyone considering buying the Property.
- the "Report" is the report, of the kind described in Part 2 of these Terms and Conditions and in the form set out in part 1 of Schedule 1 of the Housing (Scotland) Act 2006 (Prescribed Documents) Regulations 2008;
- the "Seller" is/are the proprietor(s) of the Property;
- the "Surveyor" is the author of the Report on the Property; and

² Which shall be in accordance with the current RICS Valuation Standards (the Red Book) and RICS Rules of Conduct.

- the "Surveyors" are the firm or company of which the Surveyor is an employee, director, member or partner (unless the Surveyor is not an employee, director, member or partner, when the "Surveyors" means the Surveyor) whose details are set out at the head of the Report.
- the "Energy Report" is the advice given by the accredited Energy Company, based on information collected by the Surveyor during the Inspection, and also includes an Energy Performance Certificate, in a Government approved format.

PART 2 – DESCRIPTION OF THE REPORT

2.1 THE SERVICE

The Single Survey is a Report by an independent Surveyor, prepared in an objective way regarding the condition and value of the Property on the day of the inspection, and who is a member of the Royal Institution of Chartered Surveyors. It includes an Energy Report as required by Statute and this is in the format of the accredited Energy Company. In addition, the Surveyor has agreed to supply a generic Mortgage Valuation Report.

2.2 THE INSPECTION

The Inspection is a general surface examination of those parts of the Property which are accessible: in other words, *visible and readily available for examination from ground and floor levels, without risk of causing damage to the Property or injury to the Surveyor.*

All references to visual inspection refer to an inspection from within the property at floor level and from ground level within the site and adjoining public areas, without the need to move any obstructions. Any references to left or right are taken facing the front of the property.

The Inspection is carried out with the Seller's permission, without causing damage to the building or contents. Furniture, stored items and insulation are not moved.

Unless identified in the report the Surveyor will assume that no harmful or hazardous materials have been used in the construction. The presence or possible consequences of any site contamination will not be researched.

The Surveyor will not carry out an asbestos inspection, and will not be acting as an asbestos inspector in completing a Single Survey of properties that may fall within the Control of Asbestos in the Workplace Regulations. In the case of flats it will be assumed that there is a duty holder, as defined in the Regulations and that a Register of Asbestos and effective Management Plan is in place, which does not require any expenditure, or pose a significant risk to health. No enquiry of the duty holder will be made.

2.3 THE REPORT

The Report will be prepared by the Surveyor who carried out the property inspection and will describe various aspects of the property as defined by the headings of the Single Survey report with the comments being general and unbiased. The report on the location, style and condition of the property, will be concise and will be restricted to matters that could have a material effect upon value and will omit items that, in the Surveyor's opinion, are not

significant. If certain minor matters are mentioned, it should not be interpreted that the property is free of any other minor defects.

Throughout the report, the following repair categories will be used to give an overall opinion of the state of repair and condition of the property.

- 2.3.1 <u>Category 3</u>: Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.
- 2.3.2 <u>Category 2</u>: Repairs or replacement requiring future attention, but estimates are still advised.
- 2.3.3 <u>Category 1</u>: No immediate action or repair is needed.

WARNING: If left unattended, even for a relatively short period, Category 2 repairs can rapidly develop into more serious Category 3 repairs. The existence of Category 2 or Category 3 repairs may have an adverse effect on marketability, value and the sale price ultimately achieved for the property. This is particularly true during slow market conditions when the effect can be considerable.

Parts of the property, which cannot be seen or accessed, will not be reported upon and this will be stated. If the Surveyor suspects that a defect may exist within an unexposed area and which could have a material effect upon the value, he may recommend further investigation by specialist contractors.

2.4 SERVICES

Surveyors are not equipped or qualified to test the services and therefore no comment can be interpreted as implying that the design, installation and function of the services are in accordance/compliance with regulations, safety and efficiency expectations. However, comment is made where there is cause to suspect significant defects or shortcomings with the installations. No tests are made of any services or appliances.

2.5 ACCESSIBILITY

A section is included to help identify the basic information interested parties need to know to decide whether to view a property.

2.6 ENERGY REPORT

A section is included that makes provision for an Energy Report, relative to the property. The Surveyor will collect physical data from the property and provide such data in a format required by an accredited Energy Company. The Surveyor cannot of course accept liability for any advice given by the Energy Company.

2.7 VALUATION AND CONVEYANCER ISSUES

The last section of the Report contains matters considered relevant to the Conveyancer (Solicitor). It also contains the Surveyor's opinion both of the market value of the property and of the re-instatement cost, as defined below.

"Market Value" The estimated amount for which a property should exchange on the date of valuation between a willing buyer and a willing seller in an

arm's-length transaction after proper marketing wherein the parties had each acted knowledgeably, prudently and without compulsion. In arriving at the opinion of the Market Value the Surveyor also makes various standard assumptions covering, for example, vacant possession; tenure and other legal considerations; contamination and hazardous materials; the condition of un-inspected parts; the right to use mains services; and the exclusion of curtains, carpets etc. from the valuation. In the case of flats, the following further assumptions are made that:

- *There are rights of access and exit over all communal roadways, corridors, stairways etc. and to use communal grounds, parking areas, and other facilities;
- *There are no particularly troublesome or unusual legal restrictions;
- *There is no current dispute between the occupiers of the flats or any outstanding claims or losses; and the costs of repairs to the building are shared among the co-proprietors on an equitable basis.

Any additional assumption, or any found not to apply, is reported.

"Re-instatement cost" is an estimate for insurance purposes of the current cost of rebuilding the Property in its present form unless otherwise stated. This includes the cost of rebuilding the garage and permanent outbuildings, site clearance and professional fees, but excludes VAT (except on the fees).

Sellers or prospective Purchasers may consider it prudent to instruct a reinspection and revaluation after a period of 12 weeks (or sooner if appropriate) to reflect changing circumstances in the market and/or in the physical condition of the Property

1. INFORMATION AND SCOPE OF INSPECTION

This section tells you about the type, accommodation, neighbourhood, age and construction of the property. It also tells you about the extent of the inspection and highlights anything that the Surveyor could not inspect.

All references to visual inspection refer to an inspection from within the property without moving any obstructions and externally from ground level within the site and adjoining public areas. Any references to left or right in a description of the exterior of the property refer to the view of someone standing facing that part of the property from the outside.

The inspection is carried out without causing damage to the building or its contents and without endangering the occupiers or the Surveyor. Heavy furniture, stored items and insulation are not moved. Unless identified in the report the Surveyor will assume that no harmful or hazardous materials or techniques have been used in the construction. The presence or possible consequences of any site contamination will not be researched.

Services such as TV/cable connection, internet connection, swimming pools and other leisure facilities will not be inspected or reported on.

Description	The subjects comprise a detached, one and a half storey dwelling house.
Accommodation	The accommodation can be summarised as follows:
	Ground Floor - Entrance Vestibule, Hall, Living Room, Kitchen and Shower Room.
	First Floor - Landing, Two Bedrooms and WC Toilet.
Gross internal floor area (m2)	61 or thereby.
Neighbourhood and location	The subjects are situated in a rural location, close to Craig Highland Farm which lies east of the village of Plockton. The subjects benefit from views across Loch Carron. Surrounding properties are of a scattered rural type. The situation is fairly convenient for the village amenities available within Plockton.
Age	Circa 1900.
Weather	The weather was fair at the time of inspection.
Chimney stacks	There is a rendered chimney stack with metal flashings.
	Visually inspected with the aid of binoculars where required.
Roofing including roof space	The roof is of a pitched, ridged design comprising timber rafters clad with concrete tiles, incorporating a tiled ridge. There is a uPVC clad dormer window projection which is

	contained under a sloping tiled roof covering.
	Access into the roof void area was undertaken via two ceiling hatches within each of the bedrooms.
	Sloping roofs were visually inspected with the aid of binoculars where required. Roof spaces were visually inspected and were entered where there was safe and reasonable access, normally defined as being from a 3m ladder within the property. If this is not possible, then physical access to the roof space may be taken by other means if the Surveyor deems it safe and reasonable to do so.
Rainwater fittings	Gutters and downpipes are of uPVC manufacture.
	Visually inspected with the aid of binoculars where required.
Main walls	The main original walls at ground floor level are consistent with being of a rendered solid stone construction. Walls are first floor level are of a rendered cavity blockwork construction.
	Visually inspected with the aid of binoculars where required. Foundations and concealed parts were not exposed or inspected.
Windows, external doors and joinery	The windows are of a sealed unit, double glazed, timber casement pattern.
	The front entrance door is of timber manufacture.
	Roofline soffits and fascia boards are formed in timber.
	Internal and external doors were opened and closed where keys were available. Random windows were opened and closed where possible. Doors and windows were not forced open.
External decorations	The external decorations are painted.
	Visually inspected.
Conservatories / porches	Not applicable.
Communal areas	Not applicable.
Garages and permanent	To the side of the property there is a detached store which we have assumed is of a rendered blockwork construction

outbuildings	contained under a pitched and tiled roof covering. We would point out that no access was obtained into the outbuilding at the time of inspection.
	Circulation areas visually inspected.
Outside areas and boundaries	There is garden ground lying to the front and side of the property which is sloping in nature. Garden areas are laid to grass and shrubbery.
	There is a gravel surfaced driveway lying to the front of the property which provides off-street parking.
	The boundaries, where seen, comprise post and wire fencing with a stone retaining wall at the rear. We would recommend that the exact extent of the garden grounds are ascertained by reference to the title deeds.
	Visually inspected.
Ceilings	The ceilings are plasterboard lined.
	Visually inspected from floor level.
Internal walls	Internal walls are plasterboard lined.
	Visually inspected from floor level. Using a moisture meter, walls were randomly tested for dampness where considered appropriate.
Floors including sub floors	Flooring is of floating timber construction at ground floor and suspended timber construction at first floor level.
	There is no sub-floor area.
	Surfaces of exposed floors were visually inspected. No carpets or floor coverings were lifted.
Internal joinery and kitchen fittings	The internal joinery is of a varnished softwood pattern, comprising timber panel and glazed timber doors.
	The internal stair is of timber manufacture.
	There is a fitted kitchen which has both floor and wall mounted units.
	Built-in cupboards were looked into but no stored items were moved. Kitchen units were visually inspected excluding appliances.

Chimney breasts and fireplaces	There is a stove installed at the fireplace within the living room comprising a tiled surround and hearth.
	Visually inspected. No testing of the flues or fittings was carried out.
Internal decorations	The internal decorations are painted.
	Visually inspected.
Cellars	Not applicable.
Electricity	Mains electricity is connected.
	The electricity meter is located externally within a service box to the side of the property, whilst the consumer unit is installed within the understairs cupboard.
	Accessible parts of the wiring were visually inspected without removing fittings. No tests whatsoever were carried out to the system or appliances. Visual inspection does not assess any services to make sure they work properly and efficiently and meet modern standards. If any services are turned off, the Surveyor will state that in the report and will not turn them on.
Gas	Not applicable.
Water, plumbing and bathroom fittings	Water is from the mains supply. The plumbing installation where seen, comprises copper distribution pipes, together with uPVC wastepipes.
	At ground floor level, there is a mixed colour three piece shower room suite having an electric shower installed. At first floor level there is a white WC and wash hand basin within the toilet.
	Visual inspection of the accessible pipework, water tanks, cylinders and fittings without removing any insulation. No tests whatsoever were carried out to the system or appliances.
Heating and hot water	There is no central heating system, however, the subjects do benefit from electric storage/panel heaters.
	Domestic hot water is provided by an electric immersion heater fixed to the hot water tank which is installed within the shower room cupboard.
	Visually inspected.

	No tests whatsoever were carried out to the system or appliances.
Drainage	Drainage is assumed to be to a private septic tank. This was not located.
	Drainage covers etc were not lifted. Neither drains nor drainage systems were tested.
Fire, smoke and burglar alarms	There are smoke alarms installed. Visually inspected. No tests whatsoever were carried out to the system or appliances. The new Fire and Smoke Alarm Standard came in to force in February 2022. This new standard requires a smoke alarm to be installed in the room most frequently used for living purposes and in every circulation space on each floor. A heat alarm also needs to be installed in each kitchen. The alarms need to be ceiling mounted and interlinked. Where there is a carbon-fuelled appliance such as a boiler, open fire or wood burner a carbon monoxide detector is also
Any additional limits to	required. The purchaser should satisfy themselves in this regard. A restricted inspection was possible only of the roof space
inspection	due to accessibility and insulation materials. Not all windows and doors were tested at the time of inspection. It is outwith the scope of this inspection to determine whether or not asbestos based products are present within the property. Asbestos was widely used in the building industry until around 1999, when it became a banned substance. If you have any concerns you should engage the services of a qualified asbestos surveyor. An inspection for Japanese Knotweed was not carried out. This is a plant which is subject to control regulation, is considered to be invasive and one which can render a property unsuitable for some mortgage lenders. It is therefore assumed that there is no Japanese Knotweed within the boundaries of the property or its neighbouring property. Identification of Japanese Knotweed is best undertaken by a specialist contractor. If it exists removal must be undertaken in a controlled manner by specialist contractors. This can prove to be expensive.

	It should be appreciated that the Home Report inspection is a non-disruptive visual inspection of the property as at the date of inspection and that we are unable to inspect parts of the property which are concealed or covered by floor coverings or contents in place at that time. Once vacant, defects may be apparent that could not be detected during our survey. Changing weather conditions can also affect aspects of the property which would not be apparent at the time of inspection.
--	--

Sectional Diagram showing elements of a typical house



Reference may be made in this report to some or all of the above component parts of the property. This diagram may assist you in locating and understanding these items.

	1	Chimney pots
	2	Coping stone
	3	Chimney head
	4	Flashing
	5	Ridge ventilation
	6	Ridge board
	1	Slates / tiles
	8	Valley guttering
	9	Dormer projection
	10	Dormer flashing
	11	Dormer cheeks
	12	Sarking
•	13	Roof felt
	14	Trusses
	15	Collar
	16	Insulation
	17	Parapet gutter
	18	Eaves guttering
	19	Rainwater downpipe
	20	Verge boards /skews
	21	Soffit boards
	22	Partiton wall
	23	Lath / plaster
	24	Chimney breast
	25	Window pointing
	26	Window sills
	27	Rendering
	28	Brickwork / pointing
	29	Bay window projection
	30	Lintels
	31	Cavity walls / wall ties
	32	Subfloor ventilator
	33	Damp proof course
	34	Base course
	35	Foundations
	36	Solum
	37	Floor joists
	38	Floorboards
	39	Water tank
	40	Hot water tank

2. CONDITION

This section identifies problems and tells you about the urgency of any repairs by using one of the following 3 categories:

Category 3	Category 2	Category 1
Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.	Repairs or replacement requiring future attention, but estimates are still advised.	No immediate action or repair is needed.

Structural movement	
Repair category:	
Notes:	At the time of our inspection there was no evidence of significant structural movement noted to affect the property within the limits of our inspection.

Dampness, rot and infestation		
Repair category:		
Notes:	There was no evidence found of significant dampness, rot or infestation within those areas of the property available for inspection.	

Chimney stacks	
Repair category:	2
Notes:	Weathering was noted to the chimney stack render.
	There is a temporary cover over the chimney pot.

Roofing including roof space		
Repair category:	2	

Category 3	Category 2	Category 1
Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.	Repairs or replacement requiring future attention, but estimates are still advised.	No immediate action or repair is needed.

Notes:	The roof covering is now of an age where ongoing and regular maintenance will be required and it would be prudent to seek the advice of a roofing contractor to comment on its current condition and expected lifespan.
	Evidence of condensation was noted within the roof void and ventilation should be improved. The situation should be monitored in the future.

Rainwater fittings		
Repair category:		
Notes:	At the time of our inspection there was no evidence of damp staining/water staining on wall surfaces which would indicate leakage. It should be noted that it was not raining at the time of our inspection.	
	In accordance with good maintenance practice, gutters should be regularly cleared of vegetation and debris.	

Main walls	
Repair category:	2
Notes:	Cracking was noted to the render in areas and there is a localised section of boss render to the gable wall.

Windows, external doors and joinery		
Repair category:	2	
Notes:	Seals to some of the double glazed windows have failed causing condensation between the panes.	

Category 3	Category 2	Category 1
Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.	Repairs or replacement requiring future attention, but estimates are still advised.	No immediate action or repair is needed.

Windows can be problematic and over time the operation of the
windows can be affected and opening mechanisms damaged. It is
therefore likely that maintenance/ repair will be required as part of
an ongoing maintenance programme.

External decorations	
Repair category:	
Notes:	The external decorations are generally in fair order. Regular repainting will be required if these areas are to be maintained in satisfactory condition.

Conservatories / porches	
Repair category:	
Notes:	Not applicable.

Communal areas	
Repair category:	
Notes:	Not applicable.

Garages and permanent outbuildings	
Repair category:	2
Notes:	Moss was noted to the roof covering and the gutters require to be cleared.

Category 3	Category 2	Category 1
Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.	Repairs or replacement requiring future attention, but estimates are still advised.	No immediate action or repair is needed.

As mentioned previously, no access was obtained into the
outbuilding at the time of inspection.

Outside areas and boundaries	
Repair category:	2
Notes:	Boundaries/retaining walls will require repairs and maintenance.
	There are loose slabs at the steps to the entrance door and corrosion was evident to the railings at the entrance steps.
	The access track from the western boundary is rough.

Ceilings	
Repair category:	
Notes:	Within the limits of our inspection these generally appeared in fair condition consistent with age. During redecoration some plaster filling/repair may be required.

Internal walls	
Repair category:	
Notes:	The internal walls are largely covered with decorative finishes. During routine redecoration some plaster filling may be necessary.

Floors including sub-floors

Category 3	Category 2	Category 1
Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.	Repairs or replacement requiring future attention, but estimates are still advised.	No immediate action or repair is needed.

Repair category:	2
Notes:	Due to fitted carpets and floor coverings no detailed inspection was possible of the floor timbers and accordingly we cannot guarantee their soundness or otherwise.
	It would appear that some of the flooring has been replaced previously.
	Positive moisture meter readings were evident to flooring within the kitchen.

Internal joinery and kitchen fittings	
Repair category:	
Notes:	The internal joinery is generally in keeping with the age and type of property and appeared in fair condition consistent with age.
	General wear and tear was noted to kitchen units and finishes.

Chimney breasts and fireplaces	
Repair category:	
Notes:	It is assumed that the wood/multi fuel apparatus has been installed in accordance with the manufacturer's recommendations in particular regard to flueing and ventilation. The appliance was not tested.

Internal decorations		
Repair category:	1	

Category 3	Category 2	Category 1
Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.	Repairs or replacement requiring future attention, but estimates are still advised.	No immediate action or repair is needed.

notes.	The property appears in fair decorative condition consistent with age (although it is recognised that on taking occupancy home owners may consider redecoration).
	owners may consider redecoration.

Cellars	
Repair category:	
Notes:	Not applicable.

Electricity	
Repair category:	2
Notes:	The electricity supply was turned off at the time of inspection.
	The Institution of Engineering and Technology recommends that inspections and testing are undertaken at least every ten years and on a change of occupancy. It should be appreciated that only the most recently constructed or re-wired properties will have installations which fully comply with IET regulations.

Gas	
Repair category:	
Notes:	Not applicable.

Water, plumbing and bathroom fittings	
Repair category:	

Category 3	Category 2	Category 1
Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.	Repairs or replacement requiring future attention, but estimates are still advised.	No immediate action or repair is needed.

Notes:	Sanitary goods are showing typical signs of age related wear and tear. As such there is an increased risk of water spillage to
	concealed areas and it would be prudent to ensure these are maintained in a watertight condition.

Heating and hot water		
Repair category:	2	
Notes:	The storage heater within the living room is of an older manufacture.	
	Corrosion was noted to the heated towel rail within the shower room.	

Drainage	
Repair category:	
Notes:	Drainage, we assume is to an exclusive septic tank. This was not located. It should be ensured that appropriate registration documents are available.

Category 3	Category 2	Category 1
Urgent repairs or replacement are needed now. Failure to deal with them may cause problems to other parts of the property or cause a safety hazard. Estimates for repairs or replacement are needed now.	Repairs or replacement requiring future attention, but estimates are still advised.	No immediate action or repair is needed.

Set out below is a summary of the condition of the property which is provided for reference only. You should refer to the comments above for detailed information

Structural movement	1
Dampness, rot and infestation	1
Chimney stacks	2
Roofing including roof space	2
Rainwater fittings	1
Main walls	2
Windows, external doors and joinery	2
External decorations	1
Conservatories / porches	
Communal areas	
Garages and permanent outbuildings	2
Outside areas and boundaries	2
Ceilings	1
Internal walls	1
Floors including sub-floors	2
Internal joinery and kitchen fittings	1
Chimney breasts and fireplaces	1
Internal decorations	1
Cellars	
Electricity	2
Gas	
Water, plumbing and bathroom fittings	1
Heating and hot water	2
Drainage	1

Remember

The cost of repairs may influence the amount someone is prepared to pay for the property. We recommend that relevant estimates and reports are obtained in your own name.

Warning

If left unattended, even for a relatively short period, Category 2 repairs can rapidly develop into more serious Category 3 repairs. The existence of Category 2 or Category 3 repairs may have an adverse effect on marketability, value and the sale price ultimately achieved for the property. This is particularly true during slow market conditions where the effect can be considerable.

3. ACCESSIBILITY INFORMATION

Guidance Notes on Accessibility Information

<u>Three steps or fewer to a main entrance door of the property:</u> In flatted developments the 'main entrance' would be the flat's own entrance door, not the external door to the communal stair. The 'three steps or fewer' are counted from external ground level to the flat's entrance door. Where a lift is present, the count is based on the number of steps climbed when using the lift.

<u>Unrestricted parking within 25 metres</u>: For this purpose, 'Unrestricted parking' includes parking available by means of a parking permit. Restricted parking includes parking that is subject to parking restrictions, as indicated by the presence of solid yellow, red or white lines at the edge of the road or by a parking control sign, parking meters or other coinoperated machines.

1. Which floor(s) is the living accommodation on?	Ground & First Floor
2. Are there three steps or fewer to a main entrance door of the property?	[]YES [x]NO
3. Is there a lift to the main entrance door of the property?	[]YES [x]NO
4. Are all door openings greater than 750mm?	[]YES [x]NO
5. Is there a toilet on the same level as the living room and kitchen?	[x]YES []NO
6. Is there a toilet on the same level as a bedroom?	[x]YES []NO
7. Are all rooms on the same level with no internal steps or stairs?	[]YES [x]NO
8. Is there unrestricted parking within 25 metres of an entrance door to the building?	[x]YES []NO

4. VALUATION AND CONVEYANCER ISSUES

This section highlights information that should be checked with a solicitor or licensed conveyancer. It also gives an opinion of market value and an estimated re-instatement cost for insurance purposes.

Matters for a solicitor or licensed conveyancer

The valuation is made on the assumption that any alterations that may have been carried out to the property satisfy all relevant legislation and have full certification where appropriate. While not necessarily an exhaustive list, alterations noted at the time of our inspection include the renovation of the original dwelling and subsequent extension at first floor level and the front entrance projection.

We are unaware of any adverse planning proposals affecting the subjects although this should be confirmed by obtaining a Property Enquiry Certificate.

Drainage, we assume is to an exclusive septic tank. This was not located. It should be ensured that appropriate registration documents are available.

There is a shared access road leading to the property. The conveyancer should check the legal arrangements are adequate.

Absolute Ownership assumed. We are unaware of any easements, servitudes or rights of way which may adversely affect the property. This point should be confirmed by reference to the Title Deeds.

It is recommended that where repairs, defects or maintenance items have been identified, particularly categorised as a 2 or 3, interested parties make appropriate enquiries in order to satisfy themselves of potential costs and the extent of the works required prior to submitting a legal offer to purchase.

Estimated re-instatement cost (£) for insurance purposes

£225,000

TWO HUNDRED AND TWENTY FIVE THOUSAND POUNDS STERLING

Valuation (£) and market comments

£205,000

We are of the opinion that the market value of the subjects all as previously described and on a vacant possession basis would be fairly stated in the region of £205,000 (TWO HUNDRED AND FIVE THOUSAND POUNDS STERLING).

Our valuation reflects current market conditions relating to this area. We would assume that current trends will prevail at the ultimate date of disposal with no adverse or onerous matters being introduced into the market during the intervening period which would have a detrimental effect on price.

Report author:	Kyle Davidson, Bsc (Hons) MRICS
Company name:	Graham & Sibbald LLP - Inverness
Address:	4 Ardross Street Inverness IV3 5NN
Signed:	Electronically Signed: 233905-b5d7eabd-18da
Date of report:	08/06/2023

PART 2.

MORTGAGE VALUATION REPORT

Includes a market valuation of the property.





Mortgage Valuation Report

Property:	Bonnie View Craig, Plockton IV52 8UB	Client: Mr. Cra Tenure: Absol	ig Grant ute Ownership
Date of Inspection:	06/06/2023	Reference:	KD2023060015

This report has been prepared as part of your instructions to carry out a Single Survey on the property referred to above. The purpose of this report is to summarise the Single Survey for the purpose of advising your lender on the suitability of the property for mortgage purposes. The decision as to whether mortgage finance will be provided is entirely a matter for the lender. You should not rely on this report in making your decision to purchase but consider all the documents provided in the Home Report. Your attention is drawn to the additional comments elsewhere within the report which set out the extent and limitations of the service provided. This report should be read in conjunction with the Single Survey Terms and Conditions (with MVR). In accordance with RICS Valuation – Global Standards 2017 this report is for the use of the party to whom it is addressed or their named client or their nominated lender. No responsibility is accepted to any third party for the whole or any part of this report may be included in any document, circular or statement without prior approval in writing from the surveyor.

1.0

LOCATION

The subjects are situated in a rural location, close to Craig Highland Farm which lies east of the village of Plockton. The subjects benefit from views across Loch Carron. Surrounding properties are of a scattered rural type. The situation is fairly convenient for the village amenities available within Plockton.

2.0	DESCRIPTION	2.1 Age:	Circa 1900.				
The subjects of	The subjects comprise a detached, one and a half storey dwelling house.						
3.0	CONSTRUCTION						
Walls:- The main original walls at ground floor level are consistent with being of a rendered solid stone construction. Walls are first floor level are of a rendered cavity blockwork construction.							
Roof:- The roo	Roof:- The roof is of a pitched, ridged design clad with concrete tiles.						

4.0 ACCOMMODATION

The accommodation can be summarised as follows:

Ground Floor - Entrance Vestibule, Hall, Living Room, Kitchen and Shower Room.

First Floor - Landing, Two Bedrooms and WC Toilet.

5.0	SERVICES (No tests have been applied to any of the services)						
Water:	Mains	Electricity:	Mains	Gas:	None	Drainage:	Private

Central Heati	ng:	None					
6.0	OUTBUILDIN	GS					
Garage:		None					
Others: Detached store							
7.0	of any woodw The report can defects, partic Where defects accurate estin purchase. Ge	GENERAL CONDITION - A building survey has not been carried out, nor has any inspection been made of any woodwork, services or other parts of the property which were covered, unexposed or inaccessible. The report cannot therefore confirm that such parts of the property are free from defect. Failure to rectify defects, particularly involving water penetration may result in further and more serious defects arising. Where defects exist and where remedial work is necessary, prospective purchasers are advised to seek accurate estimates and costings from appropriate Contractors or Specialists before proceeding with the purchase. Generally we will not test or report on boundary walls, fences, outbuildings, radon gas or site contamination.					
•	ondition of the p intenance are re		s consistent with	n its age and construction type	, although some	e works or	
8.0	ESSENTIAL I property)		(as a condition	n of any mortgage or, to preser	ve the condition	of the	
In our opinion,	there are no es	sential repair wo	orks considered	necessary.			
8.1 Retention	recommended	d:	0				
9.0	ROADS &FO	OTPATHS					
There is a sha way are in exi	•	ate road leadin	g to the property	/ of which we have assumed th	nat all necessar	y rights of	
10.0	BUILDINGS I (£):	NSURANCE	225,000	GROSS EXTERNAL FLOOR AREA	71	Square metres	
	This figure is an opinion of an appropriate sum for which the property and substantial outbuildings should be insured against total destruction on a re-instatement basis assuming reconstruction of the property in its existing design and materials. Furnishings and fittings have not been included. No allowance has been included for inflation during the insurance period or during re-construction and no allowance has been made for VAT, other than on professional fees. Further discussions with your insurers is advised.						
11.0	GENERAL RI	EMARKS					
relevant legisland noted at the time	ation and have f	full certification ction the formation the f	where appropria	s that may have been carried o ate. While not necessarily an e the original dwelling and subse	xhaustive list, a	Iterations	
	are of any adver operty Enquiry (posals affecting	the subjects although this sho	ould be confirme	ed by	
-	assume is to an ocuments are av	•	c tank. This wa	s not located. It should be ensu	ured that approp	oriate	
There is a sha adequate.	red access road	d leading to the	property. The c	onveyancer should check the l	legal arrangeme	ents are	
				ments, servitudes or rights of v nce to the Title Deeds.	vay which may a	adversely	
2 or 3, interest		e appropriate ei	nquiries in order	ce items have been identified, r to satisfy themselves of poter se.			
12.0		ning proposals,		ossession and that the propert s, title restrictions or servitude			

	necessary Local Authority consents, which may have been required, have been sought and obtained. No investigation of any contamination on, under or within the property has been made as we consider such matters to be outwith the scope of this report. All property built prior to the year 2000 may contain asbestos in one or more of its components or fittings. It is impossible to identify without a test. It is beyond the scope of this inspection to test for asbestos and future occupants should be advised that if they have any concerns then they should ask for a specialist to undertake appropriate tests.					
12.1	Market Value condition (£)	•	£205,000 TWO HUNDRED AND FIVE THOUSAND POUND STERLING			
12.2	Market Value completion o works (£):					
12.3	Suitable security for normal mortgage purposes?		Yes			
12.4	Date of Valuation: 06/06/2023					
Signature:		Electronically	Signed: 233905	5-b5d7eabd-18da		
Surveyor:	Kyle Davidsor	ı	Bsc (Hons) M	RICS	Date:	08/06/2023
Graham	Graham & Sibbald LLP - Inverness					
Office:	4 Ardross Street Inverness IV3 5NN		Tel: 01463 236 977 Fax: email: inverness@g-s.co.u	k		



ENERGY **Report**

A report on the energy efficiency of the property.



energy report

energy report on:

Property address	Bonnie View Craig, Plockton IV52 8UB
------------------	--

Customer Mr. Craig Grant	
--------------------------	--

Customer address	Bonnie View Craig, Plockton IV52 8UB

Prepared by	Kyle Davidson, Bsc (Hons) MRICS Graham & Sibbald LLP - Inverness

Energy Performance Certificate (EPC)

Scotland

Dwellings

BONNIE VIEW, CRAIG, PLOCKTON, IV52 8UB

Dwelling type:	Detached house	
Date of assessment:	06 June 2023	
Date of certificate:	07 June 2023	
Total floor area:	61 m ²	
Primary Energy Indicator:	769 kWh/m²/year	

Reference number: Type of assessment: Approved Organisation: Main heating and fuel:


2900-7664-0122-1005-1673 RdSAP, existing dwelling Elmhurst Electric storage heaters

You can use this document to:


- Compare current ratings of properties to see which are more energy efficient and environmentally friendly
- Find out how to save energy and money and also reduce CO₂ emissions by improving your home

Estimated energy costs for your home for 3 years*	£7,587	See your recommendations	
Over 3 years you could save*	£4,197	£4,197 report for more information	

 * based upon the cost of energy for heating, hot water, lighting and ventilation, calculated using standard assumptions



Very environmentally friendly - lower CO₂ emissions



Energy Efficiency Rating

This graph shows the current efficiency of your home, taking into account both energy efficiency and fuel costs. The higher this rating, the lower your fuel bills are likely to be.

Your current rating is **band E (44)**. The average rating for EPCs in Scotland is band D (61).

The potential rating shows the effect of undertaking all of the improvement measures listed within your recommendations report.

Environmental Impact (CO₂) Rating

This graph shows the effect of your home on the environment in terms of carbon dioxide (CO_2) emissions. The higher the rating, the less impact it has on the environment.

Your current rating is **band F (25)**. The average rating for EPCs in Scotland is band D (59).

The potential rating shows the effect of undertaking all of the improvement measures listed within your recommendations report.

Top actions you can take to save money and make your home more efficient

Recommended measures	Indicative cost	Typical savings over 3 years
1 Cavity wall insulation	£500 - £1,500	£876.00
2 Internal or external wall insulation	£4,000 - £14,000	£759.00
3 Floor insulation (solid floor)	£4,000 - £6,000	£486.00

A full list of recommended improvement measures for your home, together with more information on potential cost and savings and advice to help you carry out improvements can be found in your recommendations report.

To find out more about the recommended measures and other actions you could take today to stop wasting energy and money, visit greenerscotland.org or contact Home Energy Scotland on 0808 808 2282.

THIS PAGE IS THE ENERGY PERFORMANCE **CERTIFICATE WHICH MUST BE AFFIXED TO THE DWELLING AND NOT BE REMOVED UNLESS IT IS REPLACED WITH AN UPDATED CERTIFICATE**

Bonnie View, Craig, Plockton, IV52 8UB

Summary of the energy performance related features of this home

This table sets out the results of the survey which lists the current energy-related features of this home. Each element is assessed by the national calculation methodology; 1 star = very poor (least efficient), 2 stars = poor, 3 stars = average, 4 stars = good and 5 stars = very good (most efficient). The assessment does not take into consideration the condition of an element and how well it is working. 'Assumed' means that the insulation could not be inspected and an assumption has been made in the methodology, based on age and type of construction.

Element	Description	Energy Efficiency	Environmental
Walls	Sandstone or limestone, as built, partial insulation (assumed)	★★★☆☆	★★★☆☆
	Cavity wall, as built, partial insulation (assumed)	★★★☆☆	★★★☆☆
Roof	Pitched, 150 mm loft insulation	★★★★☆	★★★★☆
Floor	Solid, no insulation (assumed)	—	—
Windows	Fully double glazed	★★★☆☆	★★★☆☆
Main heating	Electric storage heaters	★★★☆☆	****
Main heating controls	Manual charge control	★★☆☆☆	*****
Secondary heating	Room heaters, dual fuel (mineral and wood)	—	_
Hot water	Electric immersion, off-peak	****	★★☆☆☆
Lighting	Low energy lighting in 30% of fixed outlets	★★★☆☆	★★★☆☆

The energy efficiency rating of your home

Your Energy Efficiency Rating is calculated using the standard UK methodology, RdSAP. This calculates energy used for heating, hot water, lighting and ventilation and then applies fuel costs to that energy use to give an overall rating for your home. The rating is given on a scale of 1 to 100. Other than the cost of fuel for electrical appliances and for cooking, a building with a rating of 100 would cost almost nothing to run.

As we all use our homes in different ways, the energy rating is calculated using standard occupancy assumptions which may be different from the way you use it. The rating also uses national weather information to allow comparison between buildings in different parts of Scotland. However, to make information more relevant to your home, local weather data is used to calculate your energy use, CO₂ emissions, running costs and the savings possible from making improvements.

The impact of your home on the environment

One of the biggest contributors to global warming is carbon dioxide. The energy we use for heating, lighting and power in our homes produces over a quarter of the UK's carbon dioxide emissions. Different fuels produce different amounts of carbon dioxide for every kilowatt hour (kWh) of energy used. The Environmental Impact Rating of your home is calculated by applying these 'carbon factors' for the fuels you use to your overall energy use.

The calculated emissions for your home are 133 kg CO₂/m²/yr.

The average Scottish household produces about 6 tonnes of carbon dioxide every year. Based on this assessment, heating and lighting this home currently produces approximately 8.1 tonnes of carbon dioxide every year. Adopting recommendations in this report can reduce emissions and protect the environment. If you were to install all of these recommendations this could reduce emissions by 6.7 tonnes per year. You could reduce emissions even more by switching to renewable energy sources.

Estimated energy costs for this home

Estimated energy costs for this nome				
	Current energy costs	Potential energy costs	Potential future savings	
Heating	£5,238 over 3 years	£2,538 over 3 years		
Hot water	£1,779 over 3 years	£516 over 3 years	You could	
Lighting	£570 over 3 years	£336 over 3 years	save £4,197	
Totals	£7,587	£3,390	over 3 years	

These figures show how much the average household would spend in this property for heating, lighting and hot water. This excludes energy use for running appliances such as TVs, computers and cookers, and the benefits of any electricity generated by this home (for example, from photovoltaic panels). The potential savings in energy costs show the effect of undertaking all of the recommended measures listed below.

Recommendations for improvement

The measures below will improve the energy and environmental performance of this dwelling. The performance ratings after improvements listed below are cumulative; that is, they assume the improvements have been installed in the order that they appear in the table. Further information about the recommended measures and other simple actions to take today to save money is available from the Home Energy Scotland hotline which can be contacted on 0808 808 2282. Before carrying out work, make sure that the appropriate permissions are obtained, where necessary. This may include permission from a landlord (if you are a tenant) or the need to get a Building Warrant for certain types of work.

Po	commended measures	Indicative cost	Typical saving	Rating after improvement		
Re	commended measures	indicative cost	per year	Energy	Environment	
1	Cavity wall insulation	£500 - £1,500	£292	E 51	F 32	
2	Internal or external wall insulation	£4,000 - £14,000	£253	D 57	F 38	
3	Floor insulation (solid floor)	£4,000 - £6,000	£162	D 61	E 43	
4	Add additional 80 mm jacket to hot water cylinder	£15 - £30	£54	D 62	E 44	
5	Low energy lighting for all fixed outlets	£35	£64	D 63	E 44	
6	High heat retention storage heaters and dual immersion cylinder	£1,200 - £1,800	£501	C 72	E 50	
7	Solar water heating	£4,000 - £6,000	£72	C 75	D 55	
8	Solar photovoltaic panels, 2.5 kWp	£3,500 - £5,500	£596	B 88	D 66	
9	Wind turbine	£15,000 - £25,000	£1403	A 115	B 89	

Alternative measures

There are alternative improvement measures which you could also consider for your home. It would be advisable to seek further advice and illustration of the benefits and costs of such measures.

- External insulation with cavity wall insulation
- Biomass boiler (Exempted Appliance if in Smoke Control Area)
- Air or ground source heat pump

Choosing the right improvement package

For free and impartial advice on choosing suitable measures for your property, contact the Home Energy Scotland hotline on 0808 808 2282 or go to www.greenerscotland.org.



About the recommended measures to improve your home's performance rating

This section offers additional information and advice on the recommended improvement measures for your home

1 Cavity wall insulation

Cavity wall insulation, to fill the gap between the inner and outer layers of external walls with an insulating material, reduces heat loss; this will improve levels of comfort, reduce energy use and lower fuel bills. The insulation material is pumped into the gap through small holes that are drilled into the outer walls, and the holes are made good afterwards. As specialist machinery is used to fill the cavity, a professional installation company should carry out this work, and they should carry out a thorough survey before commencing work to ensure that this type of insulation is suitable for this home and its exposure. They should also provide a guarantee for the work and handle any building standards issues. Further information about cavity wall insulation and details of local installers can be obtained from the National Insulation Association (www.nationalinsulationassociation.org.uk).

2 Internal or external wall insulation

Internal or external wall insulation involves adding a layer of insulation to either the inside or the outside surface of the external walls, which reduces heat loss and lowers fuel bills. As it is more expensive than cavity wall insulation it is only recommended for walls without a cavity, or where for technical reasons a cavity cannot be filled. Internal insulation, known as dry-lining, is where a layer of insulation is fixed to the inside surface of external walls; this type of insulation is best applied when rooms require redecorating. External solid wall insulation is the application of an insulant and a weather-protective finish to the outside of the wall. This may improve the look of the home, particularly where existing brickwork or rendering is poor, and will provide longlasting weather protection. Further information can be obtained from the National Insulation Association (www.nationalinsulationassociation.org.uk). It should be noted that a building warrant is required for the installation of external wall insulation. Planning permission may also be required and that building regulations apply to external insulation so it is best to check with your local authority on both issues.

3 Floor insulation (solid floor)

Insulation of a floor will significantly reduce heat loss; this will improve levels of comfort, reduce energy use and lower fuel bills. Insulating solid floors can present challenges; insulation laid on top of existing solid floors may impact on existing doors and finishes whilst lifting of a solid floor to insert insulation below will require consideration of the potential effect on both structural stability and damp proofing. It is advised to seek advice from a Chartered Structural Engineer or a registered Architect about this if unsure. Further information about floor insulation is available from many sources including www.energysavingtrust.org.uk/scotland/Insulation/Floor-insulation. Building regulations generally apply to this work and may also require a building warrant so it is best to check with your local authority building standards department.

4 Hot water cylinder insulation

Increasing the thickness of existing insulation by adding an 80 mm cylinder jacket around the hot water cylinder will help maintain the water at the required temperature; this will reduce the amount of energy used and lower fuel bills. The jacket should be fitted over the top of the existing foam insulation and over any thermostat clamped to the cylinder. Hot water pipes from the hot water cylinder should also be insulated, using pre-formed pipe insulation of up to 50 mm thickness, or to suit the space available, for as far as they can be accessed to reduce losses in summer. All these materials can be purchased from DIY stores and installed by a competent DIY enthusiast.

5 Low energy lighting

Replacement of traditional light bulbs with energy saving bulbs will reduce lighting costs over the lifetime of the bulb, and they last many times longer than ordinary light bulbs. Low energy lamps and fittings are now commonplace and readily available. Information on energy efficiency lighting can be found from a wide range of organisations, including the Energy Saving Trust (http://www.energysavingtrust.org.uk/home-energy-efficiency/lighting).

6 High heat retention storage heaters

Modern storage heaters have better insulation and are easier to control than the older type in this property. Ask for a quotation for new, high heat retention heaters with automatic charge and output controls. A dual-immersion cylinder, which can be installed at the same time, will provide cheaper hot water than the system currently installed. Installations should be in accordance with the current regulations covering electrical wiring. Ask the heating engineer to explain the options, which might also include switching to other forms of electric heating.

7 Solar water heating

A solar water heating panel, usually fixed to the roof, uses the sun to pre-heat the hot water supply. This can significantly reduce the demand on the heating system to provide hot water and hence save fuel and money. Planning permission might be required, building regulations generally apply to this work and a building warrant may be required, so it is best to check these with your local authority. You could be eligible for Renewable Heat Incentive payments which could appreciably increase the savings beyond those shown on your EPC, provided that both the product and the installer are certified by the Microgeneration Certification Scheme (or equivalent). Details of local MCS installers are available at www.microgenerationcertification.org.

8 Solar photovoltaic (PV) panels

A solar PV system is one which converts light directly into electricity via panels placed on the roof with no waste and no emissions. This electricity is used throughout the home in the same way as the electricity purchased from an energy supplier. Planning permission might be required, building regulations generally apply to this work and a building warrant may be required, so it is best to check with your local authority. The assessment does not include the effect of any Feed-in Tariff which could appreciably increase the savings that are shown on this EPC for solar photovoltaic panels, provided that both the product and the installer are certified by the Microgeneration Certification Scheme (or equivalent). Details of local MCS installers are available at www.microgenerationcertification.org.

9 Wind turbine

A wind turbine provides electricity from wind energy. This electricity is used throughout the home in the same way as the electricity purchased from an energy supplier. Wind turbines are not suitable for all properties. The system's effectiveness depends on local wind speeds and the presence of nearby obstructions, and a site survey should be undertaken by an accredited installer. Planning permission might be required and building regulations generally apply to this work and a building warrant may be required, so it is best to check these with your local authority. The assessment does not include the effect of any Feed-in Tariff which could appreciably increase the savings that are shown on this EPC for a wind turbine, provided that both the product and the installer are certified by the Microgeneration Certification Scheme (or equivalent). Details of local MCS installers are available at www.microgenerationcertification.org.

Low and zero carbon energy sources

Low and zero carbon (LZC) energy sources are sources of energy that release either very little or no carbon dioxide into the atmosphere when they are used. Installing these sources may help reduce energy bills as well as cutting carbon.

LZC energy sources present: There are none provided for this home

Your home's heat demand

In this section, you can see how much energy you might need to heat your home and provide hot water. These are estimates showing how an average household uses energy. These estimates may not reflect your actual energy use, which could be higher or lower. You might spend more money on heating and hot water if your house is less energy efficient. The table below shows the potential benefit of having your loft and walls insulated. Visit https://energysavingtrust.org.uk/energy-at-home for more information.

Heat demand	Existing dwelling	Impact of loft insulation	Impact of cavity wall insulation	Impact of solid wall insulation
Space heating (kWh per year)	13,817	(335)	(2,313)	(2,013)
Water heating (kWh per year)	1,953			

Addendum

This dwelling has stone walls and so requires further investigation to establish whether these walls are of cavity construction and to determine which type of wall insulation is best suited.

About this document

This Recommendations Report and the accompanying Energy Performance Certificate are valid for a maximum of ten years. These documents cease to be valid where superseded by a more recent assessment of the same building carried out by a member of an Approved Organisation.

The Energy Performance Certificate and this Recommendations Report for this building were produced following an energy assessment undertaken by an assessor accredited by Elmhurst (www.elmhurstenergy.co.uk), an Approved Organisation Appointed by Scottish Ministers. The certificate has been produced under the Energy Performance of Buildings (Scotland) Regulations 2008 from data lodged to the Scottish EPC register. You can verify the validity of this document by visiting www.scottishepcregister.org.uk and entering the report reference number (RRN) printed at the top of this page.

Assessor's name:	Mr. Kyle Davidson
Assessor membership number:	EES/014658
Company name/trading name:	Graham & Sibbald
Address:	4 Ardross Street
	Inverness
	IV3 5NN
Phone number:	01463 236977
Email address:	inverness@g-s.co.uk
Related party disclosure:	No related party

If you have any concerns regarding the content of this report or the service provided by your assessor you should in the first instance raise these matters with your assessor and with the Approved Organisation to which they belong. All Approved Organisations are required to publish their complaints and disciplinary procedures and details can be found online at the web address given above.

Use of this energy performance information

Once lodged by your EPC assessor, this Energy Performance Certificate and Recommendations Report are available to view online at www.scottishepcregister.org.uk, with the facility to search for any single record by entering the property address. This gives everyone access to any current, valid EPC except where a property has a Green Deal Plan, in which case the report reference number (RRN) must first be provided. The energy performance data in these documents, together with other building information gathered during the assessment is held on the Scottish EPC Register and is available to authorised recipients, including organisations delivering energy efficiency and carbon reduction initiatives on behalf of the Scottish and UK governments. A range of data from all assessments undertaken in Scotland is also published periodically by the Scottish Government. Further information on these matters and on Energy Performance Certificates in general, can be found at www.gov.scot/epc.

Advice and support to improve this property

There is support available, which could help you carry out some of the improvements recommended for this property on page 3 and stop wasting energy and money. For more information, visit greenerscotland.org or contact Home Energy Scotland on 0808 808 2282.

Home Energy Scotland's independent and expert advisors can offer free and impartial advice on all aspects of energy efficiency, renewable energy and more.





PART 4.

PROPERTY QUESTIONNAIRE

The owner of the property is required to complete this document which asks for information on the property such as 'Which council tax band?' etc.



Property Questionnaire

Property Address

Bonnie View Craig, Plockton IV52 8UB

Seller(s)

Craig Grant

Completion date of property questionnaire

05/06/2023

Note for sellers

Length of ownership		
How long have you owned the In the family since early 1960.	property?	
Council tax		
Which Council Tax band is you [x]A []B []C []D []E []F []G []H		
Parking		
What are the arrangements for parking at your property? (Please tick all that apply)		
Garage	[]	
Allocated parking space	[]	
Driveway	[X]	
Shared parking	[]	
On street	[]	
Resident permit	[]	
Metered parking	[]	
Other (please specify):		
	 How long have you owned the In the family since early 1960. Council tax Which Council Tax band is you [x]A []B []C []D []E []F []G []I Parking What are the arrangements for (Please tick all that apply) Garage Allocated parking space Driveway Shared parking On street Resident permit Metered parking 	

Conservation area

property questionnaire

4.		
	Is your property in a designated Conservation Area (that is an area of special architectural or historical interest, the character or appearance of which it is desirable to preserve or enhance)?	[]YES [x]NO []Don't know
5.	Listed buildings	
	Is your property a Listed Building, or contained within one (that is a building recognised and approved as being of special architectural or historical interest)?	[]YES [x]NO
6.	Alterations/additions/extensions	
а	(i) During your time in the property, have you carried out any structural alterations, additions or extensions (for example, provision of an extra bath/shower room, toilet, or bedroom)?	[]YES [x]NO
	If you have answered yes, please describe below the changes which you have made:	
	(ii) Did you obtain planning permission, building warrant, completion certificate and other consents for this work?	[]YES []NO
	If you have answered yes, the relevant documents will be needed by the purchaser and you should give them to your solicitor as soon as possible for checking.	
	If you do not have the documents yourself, please note below who has these documents and your solicitor or estate agent will arrange to obtain them:	
b	Have you had replacement windows, doors, patio doors or double glazing installed in your property	[]YES [x]NO
	If you have answered yes, please answer the three questions below:	
	(i) Were the replacements the same shape and type as the ones you replaced?	[]YES []NO
	(ii) Did this work involve any changes to the window or door openings?	[]YES []NO
	(iii) Please describe the changes made to the windows doors, or patio doors (with approximate dates when the work was completed):	
	Please give any guarantees which you received for this work to your solicitor or estate agent.	

7.	Central heating		
а	Is there a central heating system in your property? (Note: a partial central heating system is one which does not heat all the main rooms of the property - the main living room, the bedroom(s), the hall and the bathroom).	[]YES [x]NO []Partial	
	If you have answered yes or partial - what kind of central heating is there? (Examples: gas-fired, solid fuel, electric storage heating, gas warm air).		
	If you have answered yes, please answer the three questions below:		
	(i) When was your central heating system or partial central heating system installed?		
	(ii) Do you have a maintenance contract for the central heating system?	[]YES []NO	
	If you have answered yes, please give details of the company with which you have a maintenance contract		
	(iii) When was your maintenance agreement last renewed? (Please provide the month and year).		
8.	Energy Performance Certificate		
	Does your property have an Energy Performance Certificate which is less than 10 years old?	[x]YES []NO	
9.	Issues that may have affected your property		
а	Has there been any storm, flood, fire or other structural damage to your property while you have owned it?	[]YES [x]NO	
	If you have answered yes, is the damage the subject of any outstanding insurance claim?	[]YES []NO	
b	Are you aware of the existence of asbestos in your property?	[]YES [x]NO []Don't know	
	If you have answered yes, please give details:		
10.	Services		
а	Please tick which services are connected to your property and give details of the supplier:		
	Services Connected Suppl	ier	

property questionnaire

	Gas or liquid petroleum gas	N		
	Water mains or private water supply	Y	SCOT	TISH WATER
	Electricity	Y	SSE	
	Mains drainage	N		
	Telephone	N		
	Cable TV or satellite	N		
	Broadband	Ν		
b	Is there a septic tank system at your prop	erty?		[x]YES []NO
	If you have answered yes, please answer below:	the two questic	ons	
	(i) Do you have appropriate consents for t your septic tank?	he discharge fro	om	[x]YES []NO []Don't know
	(ii) Do you have a maintenance contract f	or your septic ta	ınk?	[]YES [x]NO
	If you have answered yes, please give details of the company with which you have a maintenance contract:			
	-			
11.	Responsibilities for shared or commor	n areas		
11. a	Responsibilities for shared or common Are you aware of any responsibility to cor anything used jointly, such as the repair of private road, boundary, or garden area? If you have answered yes, please give de	ntribute to the co f a shared drive		[]YES [x]NO []Don't know
	Are you aware of any responsibility to cor anything used jointly, such as the repair o private road, boundary, or garden area?	ntribute to the co f a shared drive tails: pair and mainte nmon areas?	·,	
а	Are you aware of any responsibility to cor anything used jointly, such as the repair of private road, boundary, or garden area? If you have answered yes, please give de Is there a responsibility to contribute to re of the roof, common stairwell or other con	ntribute to the co f a shared drive tails: pair and mainte nmon areas? tails: cement of any p	nance	[]Don't know []YES []NO
a b	Are you aware of any responsibility to cor anything used jointly, such as the repair of private road, boundary, or garden area? If you have answered yes, please give de Is there a responsibility to contribute to re of the roof, common stairwell or other con If you have answered yes, please give de Has there been any major repair or replace	ntribute to the co f a shared drive tails: pair and mainte nmon areas? tails: cement of any p the property? your neighbours ish bin or to ma	nance art of	[]Don't know []YES []NO [x]N/A
a b c	Are you aware of any responsibility to cor anything used jointly, such as the repair of private road, boundary, or garden area? If you have answered yes, please give de Is there a responsibility to contribute to re of the roof, common stairwell or other con If you have answered yes, please give de Has there been any major repair or replace the roof during the time you have owned to Do you have the right to walk over any of property- for example to put out your rubb your boundaries?	atribute to the co of a shared drive tails: pair and mainte amon areas? tails: cement of any part tails: cement of any part tails: your neighbours ish bin or to ma tails: eighbours have ple to put out the s?	nance art of s' intain the	[]Don't know []YES []NO [x]N/A []YES [x]NO

	any part of your property? (public right of way is a way over which the public has a right to pass, whether or not the land is privatelyowned.) If you have answered yes, please give details:	
	Through Road in front of house	
12.	Charges associated with your property	
а	Is there a factor or property manager for your property? If you have answered yes, please provide the name and address, and give details of any deposit held and approximate charges:	[]YES [x]NO
b	Is there a common buildings insurance policy?	[]YES [x]NO []Don't know
	If you have answered yes, is the cost of the insurance included in your monthly/annual factors charges?	
с	Please give details of any other charges you have to pay on a regular basis for the upkeep of common areas or repair works, for example to a residents' association, or maintenance or stair fund.	
13.	Specialist works	
а	As far as you are aware, has treatment of dry rot, wet rot, damp or any other specialist work ever been carried out to your property?	[]YES [x]NO
	If you have answered yes, please say what the repairs were for, whether you carried out the repairs (and when) or if they were done before you bought the property.	
b	As far as you are aware, has any preventative work for dry rot, wet rot, or damp ever been carried out to your property?	[]YES [x]NO
	If you have answered yes, please give details:	
с	If you have answered yes to 13(a) or (b), do you have any guarantees relating to this work?	[]YES []NO
	If you have answered yes, these guarantees will be needed by the purchaser and should be given to your solicitor as soon as possible for checking. If you do not have them yourself please write below who has these documents and your solicitor or estate agent will arrange for them to be obtained. You will also need to provide a description of the work carried out. This may be shown in the original estimate. Guarantees are held by:	

Guarantees

property questionnaire

14.			
а	Are there any guarantees or warranties for any of the following:		
(i)	Electrical work	[]NO []YES [x]Don't know []With title deeds []Lost	
(ii)	Roofing	[]NO []YES [x]Don't know []With title deeds []Lost	
(iii)	Central heating	[]NO []YES [x]Don't know []With title deeds []Lost	
(iv)	National House Building Council(NHBC)	[]NO []YES [x]Don't know []With title deeds []Lost	
(v)	Damp course	[]NO []YES [x]Don't know []With title deeds []Lost	
(vi)	Any other work or installations? (for example, cavity wall insulation, underpinning, indemnity policy)	[]NO []YES [x]Don't know []With title deeds []Lost	
b	If you have answered 'yes installations to which the g	' or 'with title deeds', please give details of the work or uarantee(s) relate(s):	
с	Are there any outstanding claims under any of the guarantees listed above?	[]YES [x]NO	
	If you have answered yes, please give details:		

15.	Boundaries				
	So far as you are aware, has any boundary of your property been moved in the last 10 years?	[]YES [x]NO []Don't know			
	If you have answered yes, please give details:				
16.	Notices that affect your property				
In the	In the past three years have you ever received a notice:				
а	advising that the owner of a neighbouring property has made a planning application?	[]YES [x]NO			
b	that affects your property in some other way?	[]YES [x]NO			

с	that requires you to do any maintenance, repairs or improvements to your property?	[]YES [x]NO
	If you have answered yes to any of a-c above, please give the notices to your solicitor or estate agent, including any notices which arrive at any time before the date of entry of the purchaser of your property.	

Declaration by the seller(s)/or other authorised body or person(s) I/We confirm that the information in this form is true and correct to the best of my/our knowledge and belief.

Signature(s):	Craig Grant
Capacity:	[x]Owner []Legally Appointed Agent for Owner
Date:	05/06/2023